

4A Pending Incomplete

Water Supply and/or Sewage Disposal System Construction Permit

Commonwealth of Virginia
Department of Health



Health Department

Identification Number

Map Reference

91-131-4105

621D 4-76-27A

Health Department

General Information

Water Supply System: New ☒ Repair ☐ Public ☐ FHA ☐ VA ☐ Case No. _____
Sewage Disposal System: New ☐ Repair ☐ Expanded ☐ Conditional ☐ Public ☐
Based on the application for a sewage disposal system construction permit filed in accordance with Section 2.13 E, of the Sewage Handling and Disposal Regulations and/or Section 2.13 of the Private Well Regulations a construction permit is hereby issued to:
Owner DON STANEMAN Telephone 721-2249
Address 210 SUMMER CIR., BOONES MILL, VA For a Type III-C Sewage Disposal System or Well to be constructed on/at PRIVATE DR. OFF RT 695 & 800 ON RT 695
Subdivision _____ Section/Block _____ Lot _____ Actual or estimated water use 300

DESIGN

NOTE: INSPECTION RESULTS

Water supply, existing: (describe) _____
To be installed: class III-C
cased 20' grouted 20'

Water supply location: Satisfactory yes ☒ no ☐
comments _____
G. W. 2 Received: yes ☐ no ☐ not applicable ☐

Building sewer: _____ I.D. PVC 40, or equivalent.
Slope 1.25" per 10' (minimum).
☐ Other _____

Building sewer: yes ☐ no ☐ comments
Satisfactory

Septic tank: Capacity _____ gals. (minimum).
☐ Other _____

Pretreatment unit: yes ☐ no ☐ comments
Satisfactory

Inlet-outlet structure:
PVC 40, 4" tees or equivalent.
☐ Other _____

Inlet-outlet structure: yes ☐ no ☐ comments
Satisfactory

Pump and pump station:
No ☐ Yes ☐ describe and show design.
if yes: _____

Pump & pump station: yes ☐ no ☐ comments
Satisfactory

Gravity mains: 3" or larger I.D., minimum 6" fall per 100'. 1500 lb. crush strength or equivalent.
☐ Other _____

Conveyance method: yes ☐ no ☐ comments
Satisfactory

Distribution box:
Precast concrete with _____ ports.
☐ Other _____

Distribution box: yes ☐ no ☐ comments
Satisfactory

Header lines:
Material: 4" I.D. 1500 lb. crush strength plastic or equivalent from distribution box to 2' into absorption trench.
Slope 2" minimum.
☐ Other _____

Header lines: yes ☐ no ☐ comments
Satisfactory

Percolation lines:
Gravity 4" plastic 1000 lb. per foot bearing load or equivalent, slope 2" 4" (min. max.) per 100'.
☐ Other _____

Percolation lines: yes ☐ no ☐ comments
Satisfactory

Absorption trenches:
Square ft. required _____; depth from ground surface to bottom of trench _____; aggregate size _____;
Trench bottom slope _____; center to center spacing _____; trench width _____;
Depth of aggregate _____;
Trench length _____; Number of trenches _____

Absorption trenches: yes ☐ no ☐ comments
Satisfactory

Date 7/27/91 Inspected and approved by: _____

Signature

Schematic drawing of sewage disposal and/or water supply system and topographic features.

PAGE 2 OF 3

show the lot lines of the building lot and building site, sketch of property showing any topographic features which may impact on the design of the well or sewage disposal system, including existing and/or proposed structures and sewage disposal systems and wells within 200 feet. The schematic drawing of the well site or area and/or sewage disposal system shall show sewer lines, pretreatment unit, pump station, conveyance system, and subsurface soil absorption system, reserve area, etc. When a nonpublic drinking water supply is to be permitted, show all sources of pollution within 200 feet.

☒ The information required above has been drawn on the attached copy of the sketch submitted with the application. Attach additional sheets as necessary to illustrate the design.

- ① SEE SHEET 303 FOR: SITE SKETCH & DISTANCES
- ② INSTALL CLASS III-C WELL CASED & GROUTED AT LEAST 20'.
- ③ WELL DRILLED TO CONTACT FLUID & HEALTH DEPT. PRIOR TO DRILLING - FOR INSPECTION DURING DRILLING.
- ④ WELL DRILLED TO COMPLETE GW-2 FORM WHEN NEW WELL IS DRILLED, COPY TO HEALTH DEPT. FOR RECORDS.

The sewage disposal system and/or water supply is to be constructed as specified by the permit or attached plans and specifications.

This sewage disposal system and/or well construction permit is null and void if (a) conditions are changed from those shown on the application (b) conditions are changed from those shown on the construction permit.

No part of any installation shall be covered or used until inspected, corrections made if necessary, and approved, by the local health department or unless expressly authorized by the local health dept. Any part of any installation which has been covered prior to approval shall be uncovered, if necessary, upon the direction of the Department.

Date: 6-7-91 Issued by: T. N. King

Date: 6-16-91 Reviewed by: [Signature]

Sanitarian

Supervisory Sanitarian

This Construction Permit Valid until

12-95

if FHA or VA financing

Reviewed by Date _____ Date _____

Supervisory Sanitarian

Regional Sanitarian

FT 500 PT 645

STEEP
TERRAIN

EXCAVATED
BANK

DRIVEWAY

CLIP 11' 11" 11' 11"

50'

100'

75'

EXIST-
HOUSE
SITE


SEP. TR.

D. FIELD
SEPTIC AREA

CREEK

DIWAY

BRANCH



Grid 4
Stoneman


Permit I.D. No. 91-131-4105

Tag Sheet

Application Received:
Application Reviewed:
Fee Determination
Assigned to:
Site Visit Scheduled:
Site Visit Made:
Follow-up Visit:
Follow-up Visit:
Issue/Deny Drafted :
Issue/Deny Reviewed:
Issue/Deny Countersigned:
Issue/Deny Mailed:

Initials	Date
<u>6-7-91 HW</u>	<u>6-7-91</u>
<u>LN</u>	<u>11</u>
<u>HW</u>	<u>6-7-91</u>
<u>K</u>	<u>11</u>
<u>6-7-91</u>	<u>TIVK</u>
<u>6-10-91</u>	<u>T N K</u>
<u>LN</u>	<u>LN</u>
<u>71</u>	<u>21</u>
<u>6-11-91</u>	<u>MLB</u>

J. A. 1000, sent
6-7-91
D. Stoneman, aware
91-131-4105
GAIP - 4



Commonwealth of Virginia
Application for a Sewage Disposal and/or Water Supply Permit

\$25,000 M090007

Health Department I.D. 91-131-4105

To Be Completed By The Applicant

Type sewage system: ☒ New ☐ Repair ☐ Expanded ☐ Conditional
FHA/VA yes ☐ no ☐ Case No. _____

Owner DON STONEMAN Address 210 Summer Cir Phone 721-2249
Boones Mill Va 24065

Agent _____ Address _____ Phone _____

Directions to Property 221 N. TO COPPER HILL - LEFT ON 645 (TWIN FALLS RD)
1.6 MILES TO DRIVEWAY ON RIGHT (9067 ON MAILBOX)

Subdivision _____ Section _____ Block _____ Lot _____

Other Property Identification _____

Dimensions/size of Lot/Property 38 acres

Other Application Information

I. Building/facility ☒ New ☐ Existing
Intermittent Use ☐ Yes ☒ No If yes, describe: _____

II. Residential Use ☒ Yes ☐ No
Termite Treatment ☐ Yes ☒ No
☒ Single Family ☐ Multifamily Number of Units _____ Number of Bedrooms 2
Basement ☐ Yes ☒ No
Fixtures in Basement ☐ Yes ☒ No

III. Commercial Use ☐ Yes ☒ No Describe: _____

Commercial/Wastewater ☐ Yes ☒ No Number of Patrons _____ Number of Employees _____
If yes, give volumes and describe _____

IV. Water Supply: ☐ Public ☒ New Describe: WELL
☒ Private ☐ Existing

V. Proposed Sewage Disposal Method:

Onsite Sewage Disposal System: Septic Tank Drainfield LPD Mound Other _____

Public Sewerage System _____

SITE PLAN Attach a site plan (rough sketch) showing dimensions of property, proposed and/or existing structures and driveways, underground utilities, adjacent soil absorption systems, bodies of water, drainage ways, and wells and springs within 200 feet radius of the center of the proposed building or drainfield. Distances may be paced or estimated.

ie property lines and building location are clearly marked and the property is sufficiently visible to see the topography. I give permission to the Department to enter onto the property described for the purpose of processing this application.

Donald L. Stoneman
Signature of owner/agent

6/6/91
Date

COMMONWEALTH OF VIRGINIA

WATER WELL COMPLETION REPORT

• BWCM No. _____

State Water Control Board
P. O. Box 11143
2111 North Hamilton St.
Richmond, Va. 23230

(Certification of Completion/County Permit)

County/City FLOYD

County/City Stamp

• Virginia Plane Coordinates

N

E

Latitude & Longitude

N

W

• Topo. Map No. _____

• Elevation _____ ft.

• Formation _____

• Lithology _____

• River Basin _____

• Province _____

• Type Logs _____

• Cuttings _____

• Water Analysis _____

• Aquifer Test _____

• Owner DON STONE MANT

• Well Designation or Number _____

Address 2100 SUMMIT RD

BOONVILLE

Phone _____

• Drilling Contractor Franklin Well DRL

Address 207 Rolling Hill Circle

Rocky Mount VA

Phone 3345238

WELL LOCATION: 1/4 (feet/miles) N direction of WIN FALLS RD
and 1/2 (feet/miles) W (direction) of RT 221
(If possible please include map showing location marked)

Date started 6-13-91

• Date completed 6-13-91

Type rig Rotary

SWCB Permit 91-131-410

County Permit _____

Certification of inspecting official:
This well does _____ does not
meet code/flow requirements.
S. _____
Date _____

For Office Use

Tax Map I.D. No. _____

Subdivision _____

Section _____

Block _____

Lot _____

Class Well: I _____ IIA _____

IIB _____ IIIA _____ IIIB _____

IIIC _____ IIID _____ IIIE _____

1. WELL DATA: New ☒ Reworked _____ Deepened _____

• Total depth 190 ft.

• Depth to bedrock 12 ft.

• Hole size (Also include reamed zones)

• 11 inches from 0 to 20 ft.

• 6 inches from 20 to 190 ft.

• _____ inches from _____ to _____ ft.

• Casing size (I.D.) and material

• 6 1/4 inches from PVC to 20 ft.

Material PVC

Wt. per foot _____ or wall thickness SDR 27.6 in.

• _____ inches from _____ to _____ ft.

Material _____

Wt. per foot _____ or wall thickness _____ in.

• _____ inches from _____ to _____ ft.

Material _____

Wt. per foot _____ or wall thickness _____ in.

• Screen size and mesh for each zone (where applicable)

• _____ inches from _____ to _____ ft.

• Mesh size _____ Type _____

• _____ inches from _____ to _____ ft.

• Mesh size _____ Type _____

• _____ inches from _____ to _____ ft.

• Mesh size _____ Type _____

• _____ inches from _____ to _____ ft.

• Mesh size _____ Type _____

• Gravel pack

• From _____ to _____ ft.

• From _____ to _____ ft.

• Grout

• From 0 to 20 ft. Type CEMENT

• From _____ to _____ ft. Type _____

2. WATER DATA • Water temperature _____ of

• Static water level (unpumped level measured) _____ ft.

• Stabilized measured pumping water level _____ ft.

• Stabilized yield 8 gpm after _____ hours

Natural Flow: Yes ☒ No _____ flow rate: _____ gpm

Comment on quality Clear

3. WATER ZONES: From 30 To 31

From 170 To 171 From _____ To _____

From _____ To _____ From _____ To _____

4. USE DATA:

Type of use: Drinking ☒ Livestock Watering _____

Irrigation _____ Food processing _____ Household ☒

Manufacturing _____ Fire safety _____ Cleaning _____

Recreation _____ Aesthetic _____ Cooling or heating _____

Injection _____ Other _____

• Type of facility: Domestic ☒ Public water supply _____

Public institution _____ Farm _____ Industry _____

Commercial _____ Other _____

5. PUMP DATA: Type _____ Rated H.P. _____

• Intake depth _____ Capacity _____ at _____ head

6. WELLHEAD: Type well seal _____

Pressure tank _____ gal. Loc. _____

Sample tap _____ Measurement port _____

Well vent _____ Pressure relief valve _____

Gate valve _____ Check valve (when required) _____

Electrical disconnect switch on power supply _____

7. DISINFECTION: Well disinfected ☒ yes _____ no _____

Date 6-13-91 Disinfectant used Chlorine TALS

Amount 2 cups Hours used _____

8. ABANDONMENT (where applicable) • yes _____ no ☒

Casing pulled yes _____ no _____ not applicable _____

Plugging grout From _____ to _____ material _____

OVER

Owner

BWCM No.

10. DRILLERS LOG (use additional Sheets if necessary)

13. Well lot dedicated? UD: Size _____ ft. X _____ ft.; Well house? _____
Distance to nearest pollutant source _____ ft.; Type _____
Distance to nearest property line _____ ft.; Building _____ ft.

Valley Reg. Off.
116 North Main Street
P. O. Box 268
Bridgewater, Va. 22812
703-828-2595

Piedmont Reg. Off.
4010 West Broad Street
P. O. Box 6616
Richmond, Va. 23230
804-257-1006

Southwest Reg. Off.
408 East Main Street
P. O. Box 476
Abingdon, Va. 24210
703-628-5183

Tidewater Reg. Off.
287 Pembroke Office Park
Suite 310 Pembroke No. 2
Va. Beach, Va. 23462
804-499-8742

West Central Reg. Off.
Executive Park
3312 Peters Creek Road
Roanoke, Va. 24019
703-982-7432

Northern Virginia Reg. Off.
5515 Cherokee Avenue
Suite 404
Alexandria, Va. 22312
703-750-9111

14. WATER SERVICE PIPE: Checked under _____ p.s.i. for _____ minutes. Pipe size _____ inches. Material _____

Installer _____
Date _____

15. I certify that the information contained herein is true and correct and that this well and/or system has been installed and constructed in accordance with the requirements for well construction as specified in compliance with appropriate county or independent city ordinances and the laws and rules of the Commonwealth of Virginia.

Signature Jerry Miller (Seal), Date 6-13-91
(Wall driller or authorized person) License No. _____